



Town of Whitecourt

Municipal Design Standards

Date:

November 2020



Revision Log

Revision #	Revised By	Date	Issue / Revision Description

Report Prepared By: _____

Report Reviewed By: _____

Disclaimer

These municipal engineering standards are subject to periodic update. The most current version of these standards will be posted to the Town's website at www.whitecourt.ca. Users of these standards for work in Whitecourt are required to download the latest version prior to proceeding with project design.

Contact

For general inquiries or to suggest revisions to this document, please forward a completed copy of Appendix B-4 to planning@whitecourt.ca.

Table of Contents

Statement of Qualifications and Limitations Distribution List

	page
1. General	1-1
1.1 Definitions	1-1
1.2 Objective	1-1
1.3 Scope	1-2
1.4 Interpretation	1-2
1.5 Use of These Standards	1-2
1.6 Revisions to these Standards	1-2
1.7 Proposed Changes and Items Not Covered	1-2
1.8 Requirements by Other Authorities	1-3
1.9 Area Structure Plan – Detailed Requirements	1-3
1.10 Development/Servicing Agreement Requirements	1-6
1.11 Design Review Process	1-8
1.12 Design Revisions After Approval Issued	1-9
1.13 Easements	1-9
1.14 Crossing Agreements	1-9
1.15 Control Markers and Legal Pins	1-9
1.16 Construction	1-10
1.17 Materials	1-10
1.18 Operation and Maintenance Manuals	1-10
1.19 Construction Completion Certificate	1-11
1.20 Warranty	1-11
1.21 Plan of Record Drawings	1-11
1.22 Final Acceptance Certificate	1-12
1.23 Infill and Redevelopment Projects	1-12
1.24 Abandoning Services, Mains and Other Works	1-13
1.25 Tie-Ins to Existing Service Connection Stubs	1-13
2. Drawing Standards	2-14
2.1 General	2-14
2.2 Required Drawings	2-15
3. Roadways	3-22
PART I – DESIGN	3-22
3.1 General	3-22
3.2 Definitions	3-22
3.3 Road Classification	3-22
3.4 Intersections	3-24
3.5 Cul-de-Sacs	3-24
3.6 Driveways	3-25
3.7 Pavement Structure	3-25
3.8 Asphalt Surface	3-26
3.9 Noise Attenuation	3-27
3.10 Transit Stops	3-27

3.11	Roadway Signage.....	3-27
3.12	Roadway Lighting	3-28
3.13	Pavement Markings	3-28
PART II – MATERIALS		3-35
3.14	Sub-grade Materials	3-35
3.15	Granular Base Course	3-35
3.16	Asphalt Cement	3-35
3.17	Aggregate	3-37
3.18	Asphalt Concrete Mix Design	3-38
3.19	Prime Coats and Tack Coats.....	3-39
3.20	Paving Equipment.....	3-40
3.21	Roadway Signage.....	3-41
3.22	Pavement Marking.....	3-41
PART III – CONSTRUCTION		3-43
3.23	General	3-43
3.24	Quality Assurance.....	3-43
3.25	Quality Control Testing	3-43
3.26	Site Preparation	3-45
3.27	Clearing	3-46
3.28	Grubbing.....	3-46
3.29	Topsoil Stripping and Stockpiling	3-46
3.30	Pavement and Concrete Removal.....	3-47
3.31	Fillcrete	3-47
3.32	Utility Cut Restoration	3-48
3.33	Excavation	3-48
3.34	Fill and Grade	3-49
3.35	Shallow-Buried Utility Trenches.....	3-49
3.36	Sub-grade Preparation	3-49
3.37	Base Course	3-50
3.38	Protection of Prepared Base	3-50
3.39	Asphalt Concrete Production.....	3-50
3.40	Paving.....	3-51
3.41	Joints.....	3-52
3.42	Roadway Signage.....	3-53
3.43	Pavement Marking.....	3-53
3.44	Rejected Work	3-54
4.	Curbs, Gutters, and Sidewalks.....	4-55
PART I – DESIGN		4-55
4.1	General	4-55
4.2	Sidewalks and Walkways	4-55
4.3	Curb and Gutter.....	4-56
PART II – MATERIALS		4-56
4.4	Portland Cement Concrete	4-56
4.5	Concrete Formwork	4-58
PART III – CONSTRUCTION		4-59
4.6	General	4-59
4.7	Quality Assurance.....	4-59
4.8	Quality Control Testing	4-60
4.9	Site Preparation	4-61

4.10	Clearing	4-61
4.11	Grubbing	4-61
4.12	Topsoil Stripping and Stockpiling	4-61
4.13	Excavation	4-61
4.14	Fill and Grade	4-61
4.15	Shallow-Buried Utility Trenches.....	4-61
4.16	Sub-grade Preparation	4-61
4.17	Base Course	4-61
4.18	Protection of Prepared Base	4-61
4.19	Formwork	4-61
4.20	Reinforcing.....	4-62
4.21	Pouring.....	4-63
4.22	Finishing	4-64
4.23	Crack-Control Joints	4-64
4.24	Isolation Joints	4-65
4.25	Construction Joints	4-65
4.26	Sidewalk Joints Abutting an Existing Curb	4-66
4.27	Protection.....	4-66
4.28	Curing	4-66
4.29	Backfilling.....	4-66
4.30	Tolerances	4-67
4.31	Rejected Work	4-68

5. Water Distribution System..... 5-1

PART I – DESIGN	5-1
5.1 General	5-1
5.2 Water Mains.....	5-1
5.3 Hydrants	5-3
5.4 Water Main Valves.....	5-3
5.5 Pressure Relief Valves	5-4
5.6 Water Service Connections	5-4
PART II – MATERIALS	5-5
5.7 Water Mains.....	5-5
5.8 Hydrants.....	5-6
5.9 Water Main Valves.....	5-6
5.10 Pressure Relief Valves	5-7
5.11 Water Service Connections	5-7
5.12 Cathodic Protection	5-8
5.13 Bedding and Backfill	5-8
PART III – CONSTRUCTION	5-10
5.14 General	5-10
5.15 Quality Assurance.....	5-10
5.16 Quality Control Testing	5-10
5.17 Site Preparation	5-10
5.18 Clearing	5-11
5.19 Grubbing.....	5-11
5.20 Topsoil Stripping and Stockpiling	5-11
5.21 Operating Existing Valves and Hydrants.....	5-11
5.22 Trench Excavation	5-11
5.23 Alignment and Grade.....	5-11

5.24	Pipe Bedding and Pipe Zone Backfill	5-12
5.25	Pipe Installation	5-12
5.26	Setting Hydrants	5-13
5.27	Setting Fittings and Valves	5-13
5.28	Thrust Blocks and Mechanical Joint Restraints.....	5-14
5.29	Water Service Connections	5-14
5.30	Cathodic Protection	5-15
5.31	Trench Backfill	5-16
5.32	Hydrostatic Pressure Testing and Cleaning	5-17
5.33	Inspection of Valves and Hydrants	5-19
5.34	Placing Water Mains into Service	5-19
5.35	Hydrant Flow Testing.....	5-19
6.	Wastewater Collection System	6-1
	PART I – DESIGN	6-1
6.1	General	6-1
6.2	Gravity Sewer Mains	6-1
6.3	Manholes	6-3
6.4	Wastewater Gravity Service Connections	6-3
6.5	Unapproved Connections	6-4
6.6	Lift Stations and Sewage Force Mains	6-4
	PART II – MATERIALS	6-5
6.7	Gravity Sewer Mains.....	6-5
6.8	Manholes	6-6
6.9	Wastewater Gravity Service Connections	6-7
6.10	Force Mains	6-7
6.11	Bedding and Backfill	6-7
	PART III – CONSTRUCTION	6-7
6.12	General	6-7
6.13	Quality Assurance.....	6-7
6.14	Quality Control Testing	6-8
6.15	Site Preparation	6-8
6.16	Clearing	6-8
6.17	Grubbing.....	6-8
6.18	Topsoil Stripping and Stockpiling	6-8
6.19	Trench Excavation	6-8
6.20	Alignment and Grade.....	6-8
6.21	Pipe Bedding and Pipe Zone Backfill	6-8
6.22	Pipe Installation	6-8
6.23	Setting Manholes	6-9
6.24	Wastewater Gravity Service Connections	6-10
6.25	Trench Backfill	6-11
6.26	Low Pressure Sewage Systems	6-11
6.27	Gravity Sewer Main Inspection and Testing.....	6-15
6.28	Sewer Service Inspection and Testing	6-16
6.29	Final Inspection.....	6-16
7.	Stormwater Management System	7-1
	PART I – DESIGN	7-1
7.1	General	7-1

7.2	Minor System General Design Criteria	7-1
7.3	Gravity Sewer Mains.....	7-3
7.4	Manholes	7-4
7.5	Catch Basins.....	7-5
7.6	Catch Basin Leads.....	7-5
7.7	Stormwater Service Connections	7-6
7.8	Foundation Drain Discharge Collection Sewers.....	7-7
7.9	Oil and Grit Interceptors	7-7
7.10	Lift Stations and Stormwater Force Mains	7-8
7.11	Major System General Design Criteria	7-8
7.12	Stormwater Management System Design for Infill and Redevelopment Projects.....	7-11
7.13	Storm Outfalls	7-12
PART II – MATERIALS		7-12
7.14	Storm Sewer Mains, Catch Basin Leads, and Foundation Drain Discharge Collection Sewers....	7-12
7.15	Culverts.....	7-13
7.16	Manholes	7-13
7.17	Catch Basins.....	7-14
7.18	Stormwater Service Connections	7-14
7.19	Oil and Grit Interceptors	7-14
7.20	Stormwater Force Mains	7-15
7.21	Bedding and Backfill	7-15
PART III – CONSTRUCTION		7-15
7.22	General	7-15
7.23	Quality Assurance.....	7-15
7.24	Quality Control Testing	7-15
7.25	Site Preparation	7-15
7.26	Clearing	7-15
7.27	Grubbing	7-15
7.28	Topsoil Stripping and Stockpiling	7-15
7.29	Trench Excavation	7-15
7.30	Alignment and Grade.....	7-15
7.31	Pipe Bedding and Pipe Zone Backfill	7-16
7.32	Pipe Installation	7-16
7.33	Setting Manholes	7-16
7.34	Setting Catch Basins	7-16
7.35	Stormwater Service Connections	7-16
7.36	Trench Backfill	7-16
7.37	Stormwater Main Inspection and Testing.....	7-16
7.38	Stormwater Service Inspection and Testing.....	7-16
7.39	Final Inspection of Stormwater Mains	7-16
8.	Landscaping Standards – General	8-1
8.1	Landscaping Standards.....	8-1
8.2	Park Development Guidelines	8-1
8.3	Boulevard Development Guidelines	8-1
8.4	Development Guidelines for Arterial Roads, Major Collector Roads and Subdivision Entrance Features.....	8-1
8.5	Walkway Design Guidelines.....	8-2
8.6	Major Utility Right-of-Way Design Guidelines	8-2
8.7	Public Utility Lot Design Guidelines.....	8-2

8.8	Stormwater Management Facilities in Parks Design Guidelines	8-3
8.9	Naturalization Design Guidelines	8-3
8.10	Environmental Reserve Design Guidelines	8-4
8.11	Multiple Family, Institutional, Commercial, or Industrial, Site Design Guidelines	8-4
8.12	Fencing Design Guidelines.....	8-4
8.13	Site Amenity Design Guidelines	8-4
8.14	Trail Design Guidelines	8-5
8.15	General Guidelines – Construction Inspection Process.....	8-5
8.16	Additional Guidelines – Construction Completion Certificate.....	8-5
8.17	Maintenance	8-6
8.18	Additional Guidelines – Final Acceptance Certificate.....	8-7
9.	Landscaping Standards – Sub-Grade and Topsoil.....	9-1
	PART I – DESIGN	9-1
9.1	Design Guidelines.....	9-1
9.2	Drainage Guidelines	9-1
	PART II – GENERAL	9-2
9.3	Examination	9-2
9.4	Samples	9-2
9.5	Product Delivery, Storage and Handling	9-2
9.6	Inspections.....	9-2
	PART III – PRODUCTS	9-3
9.7	Fill	9-3
9.8	Sand.....	9-3
9.9	Crushed Gravel.....	9-3
9.10	Topsoil	9-3
	PART IV - EXECUTION.....	9-4
9.11	Site Preparation	9-4
9.12	Clearing	9-4
9.13	Disposal	9-5
9.14	Salvage	9-5
9.15	Grubbing.....	9-5
9.16	Topsoil Stripping and Stockpiling	9-5
9.17	Excavation, Fill and Grade	9-6
9.18	Sub-grade Preparation	9-7
9.19	Topsoil Placement	9-7
9.20	Spreading of Topsoil – Natural Areas, ERs.....	9-8
10.	Landscaping Standards – Pathways and Trails.....	10-1
	PART I – DESIGN	10-1
10.1	Objectives	10-1
10.2	Pathway Classifications	10-1
10.3	Planning Guidelines.....	10-1
10.4	Design Guidelines	10-2
	PART II – GENERAL	10-3
10.5	Examination	10-3
10.6	Samples	10-3
10.7	Inspection	10-3
	PART III – PRODUCTS	10-4
10.8	Sub-Base	10-4

10.9	Asphalt Concrete	10-4
10.10	Signage.....	10-4
PART IV - EXECUTION.....		10-4
10.11	Asphalt Pathway Paving	10-4

11. Landscaping Standards – Plant Material 11-1

PART I – DESIGN		11-1
11.1	Minimum Setback Requirements.....	11-1
11.2	Tree Selection.....	11-1
11.3	Planting Season.....	11-4
PART II – GENERAL		11-4
11.4	Scope.....	11-4
11.5	Substitutions	11-4
11.6	Product Delivery, Storage, and Handling	11-4
11.7	Inspections.....	11-4
PART III - PRODUCTS		11-5
11.8	Plant Materials	11-5
11.9	Edger	11-6
11.10	Fertilizer	11-6
11.11	Tree Stakes, Ties, and Guys	11-6
11.12	Water	11-7
PART IV - EXECUTION.....		11-7
11.13	Planting Operations – Trees and Bare Root Plants	11-7
11.14	Planting Operations – Shrubs.....	11-7
11.15	Stakes, Ties, and Guys	11-8
11.16	Pruning.....	11-9
11.17	Construction Completion Inspection.....	11-9
11.18	Warranty	11-10
11.19	Maintenance	11-10
11.20	Final Inspection.....	11-10

12. Landscaping Standards – Mulch..... 12-11

PART I – DESIGN		12-11
PART II - GENERAL.....		12-11
12.1	Examination	12-11
12.2	Samples	12-11
12.3	Substitutions	12-11
12.4	Product Delivery, Storage, and Handling	12-11
12.5	Inspection	12-11
PART III – PRODUCTS		12-12
12.6	Organic Mulches	12-12
12.7	Inorganic Mulches.....	12-12
12.8	Prohibited Mulches	12-12
PART IV - EXECUTION.....		12-12
12.9	Installation.....	12-12
12.10	Preparation	12-12
12.11	Clean Up.....	12-12
12.12	Maintenance	12-12

13.	Landscaping Standards – Seed and Sod.....	13-1
	PART I – DESIGN	13-1
	PART II – GENERAL	13-1
	13.1 Examination	13-1
	13.2 Samples	13-1
	13.3 Product Delivery, Storage, and Handling	13-1
	13.4 Substitution	13-1
	13.5 Inspection	13-2
	PART III - PRODUCTS	13-2
	13.6 Grass Seed	13-2
	13.7 Sod.....	13-4
	13.8 Binder	13-4
	13.9 Mulch	13-4
	13.10 Fertilizer	13-4
	13.11 Water	13-5
	PART IV – EXECUTION	13-5
	13.12 Preparation	13-5
	13.13 Seeding.....	13-5
	13.14 Sodding.....	13-6
	13.15 Clean-up	13-7
	13.16 Construction Completion Inspection.....	13-7
	13.17 Maintenance	13-7
	13.18 Final Inspection.....	13-7
14.	Landscaping Standards – Site Amenities & Fencing.....	14-1
	PART I – DESIGN	14-1
	14.1 General	14-1
	14.2 Minimum Setback Requirements.....	14-2
	PART II – GENERAL	14-2
	14.3 Examination	14-2
	14.4 Product Delivery, Storage, and Handling	14-2
	14.5 Substitution	14-2
	14.6 Inspection	14-2
	PART III - PRODUCTS	14-3
	14.7 General	14-3
	14.8 Benches	14-3
	14.9 Waste Receptacles.....	14-3
	14.10 Picnic Tables	14-3
	14.11 Bollards.....	14-3
	14.12 Amenities	14-3
	PART IV – EXECUTION	14-3
	14.13 Site Amenities	14-3
	14.14 Fencing	14-3
	14.15 Construction Completion Inspection.....	14-4
	14.16 Maintenance	14-4
	14.17 Final Acceptance Inspection.....	14-4

Appendices

Appendix A. Engineering Standard Drawings

- A-01 Typical Fire Hydrant
- A-02 Buried Valve
- A-03 Water Service Connection
- A-04 Horizontal Concrete Thrust Block Detail
- A-05 Vertical Bend and Offset Thrust Block Detail
- A-06 Special Thrust Block for Disturbed Areas
- A-07 Typical Dead End Up to 300mm
- A-08 1200mm Standard Manhole (Pipes Less Than 600mm)
- A-09 Sanitary Terminal Cleanout Manhole
- A-10 Oversized Manhole (Pipes 600 mm – 900mm)
- A-11 Internal Drop Manhole
- A-12 External Drop Manhole
- A-13 Sanitary Deep Service Connection Riser Type
- A-14 Sanitary Service Connection Non-Riser Type
- A-15 Pipe Zone Bedding Details (Class A, A1, B)
- A-16 Pipe Zone Bedding Details (Class C, C1, D)
- A-17 Trench Backfill New Construction
- A-18 Trench Backfill for New Construction in High Water Tables
- A-19 Pipe Support Detail
- A-20 Safety Platform
- A-21 600mm Catch Basin (F38 Frame & Cover)
- A-22 900mm Catch Basin (F33 Frame & Cover)
- A-23 900mm Catch Basin (F51 Inlet Frame & Cover)
- A-24 Type F-51 Catch Basin Curb Treatment
- A-25 Depressed Curb at Catch Basin Locations
- A-26 Slab Tops for 1200mm Manhole
- A-27 Concrete Outfall Structure
- A-28 Screening for Inlet/Outfall Structure
- A-29 Culvert End Treatment
- A-30 Weeping Tile Discharge
- A-31 Lot Grading Details
- A-32 “CC” Stamp Location
- A-33 Local Street Residential
- A-34 Collector Street Residential
- A-35 Local Street Commercial/Industrial
- A-36 Collector Street Commercial/Industrial
- A-37 Arterial Roadway
- A-38 Cul-De-Sac Layout
- A-39 Lane Sections
- A-40 Standard Trail
- A-41 Typical Rural Cross Section
- A-42 Typical Rural Approach
- A-42A Typical Rural Cul-De-Sac
- A-43 Typical Rural Utility Layout
- A-44 Typical Rural Hydrant Approach Layout
- A-45 Dimensions for Single Arrow
- A-46 Dimensions for Double Arrow
- A-47 Dimensions for Merge Arrow
- A-47A Typical Zebra Line Crossing
- A-48 Rolled Curb & Gutter
- A-49 Straight Faced Curb & Gutter (250mm)
- A-50 Straight Faced Curb & Gutter (500mm)
- A-51 Standard Barrier Curb

A-52	Concrete Swale
A-53	Monolithic Curb, Gutter & Sidewalk
A-54	Para Ramp on Corner Type 'A'
A-55	Para Ramp on Corner Type 'B'
A-56	Para Ramp on Tangent Type 'C'
A-57	Para Ramp on Tangent Type 'D'
A-58	1.5m Separate Sidewalk
A-59	Sidewalk Joint and Finishing Details
A-60	Concrete Lane Access Details
A-61	Concrete Paving Stones

Appendix B. Construction Completion and Final Acceptances

B.1	CCC Request Form
B.1(i)	CCC Check List
B.1(ii)	Alberta Environment Information Requirements for Notification of Extensions of Water Distribution, Wastewater Collection, and Storm Drainage Systems
B.2	FAC Request Form
B.3	Development Revision Request Form
B.4	Design Revision Request Form

Appendix C. Infrastructure Summary Tables

Appendix D 3 Steps to Tree Preservation

Appendix E Landscaping Templates for Buffers and Perimeter Planting on Interior Lots

Appendix F Watermain Testing

Appendix G 4 Party Franchise Utility Location Details

Appendix H Environment Canada Rainfall Intensity, Duration, Frequency Data for Whitecourt

Appendix I Guidelines for Extended Corner Street Signs